

**GOVERNMENT OF JAMMU AND KASHMIR**  
**OFFICE OF THE CHIEF EXECUTIVE OFFICER**  
**YOUSMARG DEVELOPMENT AUTHORITY**  
 Camp Office Jabbar Complex Near Petrol Pump Bagh-i-Mehtab Srinagar

**NOTICE INVITING TENDER**  
**e.N.I.T No. 04/YDA/2015-16 Dated: -10/ 10/2015**

For and on behalf of the Governor of Jammu and Kashmir State, the Executive Engineer, Yousmarg Development Authority, hereby invites e-tenders (in Single cover System) on item rate basis from the eligible contractors registered with J&K State Govt., PWD/CPWD, Railways and other State/Central Governments for the following works:

| S. No. | Name of Work   | Est. Cost (In lacs) | Cost of Tender Documents | Earnest Money | Time of completion | Class of Contractors | M.H. of Account |
|--------|--|---------------------|--------------------------|---------------|--------------------|----------------------|-----------------|
| 1.     | Development Of Inner Road By Way Of Providing And Laying Of GSB ,WBM Grade II and In Patches/Stretches And WBM Grade III In Full (Agg. Length =2500 Mtrs.) | 16.00 lacs          | 700                      | 32000/-       | 30 Days            | AaY & BEE            | 5452-TSM Plan   |
| 2.     | Balanced Work Items of Hut no 3 and View Point at Yousmarg   | 2.25 lacs           | 300                      | 4500/-        | 30 Days            | DEE                  | --do--          |

**Position of AAA/TS: Under Submission**

**Position of funds: Demanded**

- The Bidding documents consisting of qualifying information, eligibility criteria, specification, drawing bill of quantities (B.O.Q), set of terms & conditions of contract and other details can be seen/downloaded from the departmental website [www.jktenders.gov.in](http://www.jktenders.gov.in) as per schedule of dates given below:

|     |  |   |
|-----|--|---|
| 01. | Date of issue of Tender Notice                           | 12-10-2015                                  |
| 02. | Period of downloading of bidding documents.              | 13-10-2015 to 19-10-2015                    |
| 03. | Bid submission Start date                                | 13-10-2015 from 2.00 p.m                    |
| 04. | Bid submission end date                                  | 19-10-2015 upto 2.00 pm                     |
| 05. | Deadline for receiving the hard copy (Original DD & EMD) | 20-10-2015 upto 2.00 pm in the CEO's office |
| 06. | Date & time of opening of Bids (on line)                 | 21-09-2015 at 11 am in the CEO's office     |

- Bids must be accompanied with cost of tender documents in shape of demand draft in favour of Executive Engineer Y.D.A (Tender inviting Authority) and Earnest Money/Bid Security in shape of CDR pledged to Accounts Officer Yousmarg Development Authority & income tax clearance certificate from Income Tax Department.
- The date and time of opening of Bids shall be notified on website [www.jktenders.gov.in](http://www.jktenders.gov.in) and conveyed the bidders automatically through and e-mail message on their e-mail address. The bids of responsive bidders shall be opened online on the same website in the office of the Chief Executives Officer, Yousmarg Development Authority.
- The Earnest money shall be forfeited if :
  - Any bidder/Tenderer withdraws his bid/tender during the period of bid validity or makes any modification in the terms and conditions of the bid.
  - Failure of successful bidders to furnish the required performance security whether the specified time limit.
  - Failure of successful bidder to execute the agreement within 28 days after fixation of contract.
- All Other terms and conditions shall remain same as advertised vide this office e-tender notice no. 01/YDA of 2015-16 Dated 05-06-2015 issued under endorsement no. EE/YDA/2015-16/136-41 Dated 05-06-2015.

**No. EE/YDA/2015-16/333-42**  
**Dated:10-10 -2015.**

**Sd/-**  
**Executive Engineer**  
**Yousmarg Development Authority**

**Copy to the: -**

1. Chief Executive Officer, Yousmarg Development Authority.
2. Joint Director Information Deptt, J&K State Sgr. for publishing the NIT in two leading dailies before due date.
3. Accounts Officer, Yousmarg Development Authority for information.
4. Notice Board.
5. I/C Computer Section Direction office to upload the NIT in [www.jktenders.gov.in](http://www.jktenders.gov.in).
6. All Concerned as per practice for distribution of NIT.

**ADVERTISED RATE LIST /QTY SCHEDULED FOR DEVELOPMENT OF INNER ROAD BY WAY OF PROVIDING AND LAYING OF GSB ,WBM GRADE II and IN PATCHES/STREATCHES AND WBM GRADE III IN FULL(AGG.LENGTH =2.5 KMS) ADVT. COST = 16.00 LAKHS**

| S.NO | PARTICULARS OF ITEMS   | QTY | UNIT | RATE  |
|------|--|-----|------|-------|
| 1    | Providing laying watering and compacting with (80-100) kn roller nallah muck (G S B )with aggregate size not exceeding 90 mm granular sub -base materials to specified lines grade cross -sections and density finished work to be measured including carriage of materials upto site of work complete   | 103 | CUM  | R.T.Q |
| 2    | Supplying stacking and laying of graded stone aggregate with specified stone aggregate stone screening @15.20% and binding materials including screening sorting spreading to template and consolidation with power road roller of 8-10 tonne capacity etc. Base course 63mm to 45 mmsize incl . Stone screening 13,20 mm nominal size type-A incl. Moorum binding material incl. Cost and carriage of material upto site of work complete | 68  | CUM  | R.T.Q |
| 3    | Supplying stacking and laying of graded stone aggregate with specifird stone aggregate stone screening at 22.80% and binding material @ 8% including screening sorting spreading .to template and consolidation with power road roller of 8-10 tonne capacity etc Base course with 53 mm to 22.40 mm size incl. Stone screening 11.20 mm nominal size type- B including moorum binding materials incl. Costs and carriages of material     | 684 | CUM  | R.T.Q |

Sd/-

EXECUTIVE ENGINEER  
YOUSMARG DEV.AUTHORITY

**ADVERTISE RATE LIST /QTY. SCHEDULE FOR BALANCED WORK ITEMS OF HUT NO 3 AND VIEW POINT AT YOUSMARG (ADVT.COST =2.25 LAKHS)**

| S.NO | PARTICULARS OF ITEMS   | QTY   | UNIT | RATE  |
|------|--|-------|------|-------|
| 1    | Providing and fixing M.S grills of required Pattern in frames of Windows etc .With M.S.Flates , Square or round bars etc. including primary Coat With Approved Steel Primer all Complete. Fixed To opening Wooden frames with rawl Plugs Screws etc  | 336   | kgs  | R.T.Q |
| 2    | Providing and fixing Curtain rods of 1.25 mm Thick Chromium Plated brass Plate .With Two Chromium Plated brass Brackets fixed With C.P brass screws and Wooden Pligs etc Wherever necessary Complete 25mm dia.   | 20.42 | RM   |       |
| 3    | Providing and laying in Position Cement Concrete of Specified grade excluding the Cost Centring and Shuttering.All Works upto Plinth level 1:4:8 (1 cement :4 Coarse Sand :8 graded Stone aggregate 40mm nominal size) Crushed incl. Costs and Carriage of materials involved complete.  | 6.37  | CUM  |       |
| 4    | Providing and laying in Position Cement Concrete of Specified grade excluding the Cost Centring and Shuttering.All Works upto Plinth level 1:2:4 (1 cement :2 Coarse Sand :4 graded Stone aggregate 20mm nominal size) Crushed incl. Costs and Carriage of materials involved complete.  | 2.25  | CUM  |       |
| 5    | Providing and laying vetrified Floor Tiles in different sizes.(thickness to be specified) by the manufacturer) with water absorption less than .08% with all colors and shades laid on 20 mm Thick Cement mortar 1:4(1 Cement :4 Course sand ) including grouting joints with cement and material pigments etc complete(size of the tile 60x60 cm. Selection of tiles all as directed by Engineer in charge. | 27.88 | SQMT |       |
| 6    | Providing and Fixing gang saw cut mirror Polished (premoulded and prepolished) machine cut granite of black color for steps, trends etc laid over 20 mm thick base cement mortar 1:4 (1 cement:4 sand) with joints treated with white cement mixed with maching pigment complete.  | 13.38 | SQMT |       |
| 7    | Providing and fixing of 40 mm thick inter lock demolite tiles of approved design and colour in footpath and courtyard joints to be filled and fitted with sand including rubbing and cleaning etc complete on 20mm thick bed of cement mortar 1:4 mix (1cement:4 course sand) incl cost and carriages of materials involved complete. Selection of tiles all as directed by the Engineer In-Charge.          | 55.76 | SQMT |       |

Sd/-

EXECUTIVE ENGINEER  
YOUSMARG DEV. AUTHORITY